

# Schedule 40 Conduit



Tested and Certified by NSF International  
 to **UL 651**

- Conduit is manufactured to be in conformance with NEMA TC 2 and UL 651.

---

- Designed and produced for use in both above ground and below ground applications.

---

- Product manufactured with one integral solvent-weld bell standard per length.

---

Part Number		Size	Dimensions (inches)		Minimum Wall (inches)	Approximate Weight per 100'	Standard Crate Quantity	
10'	20'		OD (Avg)	ID (Approx)			10'	20'
4005010	4005020	½"	0.840	0.60	0.109	16	6,000	12,000
4007510	4007520	¾"	1.050	0.80	0.113	21	4,400	8,800
4010010	4010020	1"	1.315	1.03	0.133	31	3,600	7,200
4012510	4012520	1 ¼"	1.660	1.36	0.140	42	3,300	6,600
4015010	4015020	1 ½"	1.900	1.59	0.145	51	2,250	4,500
4020010	4020020	2"	2.375	2.04	0.154	71	1,400	2,800
4025010	4025020	2 ½"	2.875	2.44	0.203	113	930	1,860
4030010	4030020	3"	3.500	3.03	0.216	164	880	1,760
4035010	4035020	3 ½"	4.000	3.51	0.226	197	630	1,260
4040010	4040020	4"	4.500	3.99	0.237	233	570	1,140
4050010	4050020	5"	5.563	5.01	0.258	316	380	760
4060010	4060020	6"	6.625	6.02	0.280	411	260	520