

Schedule 80 Conduit



Tested and Certified by NSF International
 to **UL 651**

- Conduit is manufactured to be in conformance with NEMA TC 2 and UL 651.

- Designed and produced for use in both above ground and below ground applications.

- Product manufactured with one integral solvent-weld bell standard per length.

Part Number		Size	Dimensions (inches)		Minimum Wall (inches)	Approximate Weight per 100'	Standard Crate Quantity	
10'	20'		OD (Avg)	ID (Approx)			10'	20'
8005010	8005020	½"	0.840	0.52	0.147	20	6,000	12,000
8007510	8007520	¾"	1.050	0.72	0.154	28	4,400	8,800
8010010	8010020	1"	1.315	0.93	0.179	41	3,600	7,200
8012510	8012520	1 ¼"	1.660	1.25	0.191	56	3,300	6,600
8015010	8015020	1 ½"	1.900	1.47	0.200	68	2,250	4,500
8020010	8020020	2"	2.375	1.90	0.218	94	1,400	2,800
8025010	8025010	2 ½"	2.875	2.28	0.276	143	930	1,860
8030010	8030020	3"	3.500	2.85	0.300	191	880	1,760
8040010	8040020	4"	4.500	3.77	0.337	280	570	1,140
8050010	8050020	5"	5.563	4.76	0.375	388	380	760
8060010	8060020	6"	6.625	5.70	0.432	533	260	520